SAFETY REGULATIONS

ALL EXCAVATION AND METHODS OF CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE MARYLAND OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (MOSHA) STANDARDS AS SET FORTH IN THE LATEST VERSION OF THE CODE OF MARYLAND REGULATIONS

CONSTRUCTION NOTIFICATION

The Contractor/Owner is to notify the County SOIL CONSERVATION DISTRICT at least 72 hours prior to construction to facilitate any scheduling, layout, or preliminary mobilization necessary to ensure proper construction inspection to enable appropriate certification of the project.

It is the Landowner's responsibility to obtain all County, State, and Federal permits that may be needed, and to maintain this structure and related regulations.

THERE WILL BE NO CHANGES IN SPECIFICATION, DIMENSIONS, OR MATERIALS UNLESS APPROVED BY THE ENGINEER RESPONSIBLE FOR THIS DRAWING. THE DRAWINGS ARE PREPARED COOPERATIVELY BY THE NATURAL RESOURCE CONSERVATION SERVICE FOR THE NAMED LANDOWNER.

CONSTRUCTION FOUND NOT IN ACCORDANCE WITH THESE DRAWINGS AND SPECIFICATIONS SHALL VIOLATE THE COOPERATIVE AGREEMENT AND ALL DRAWINGS, SPECIFICATIONS, AND QUANTITIES ESTIMATE SHALL IMMEDIATELY BE RETURNED TO THE LOCAL NRCS OFFICE.

GENERAL NOTES:

- PLEASE CONTACT THE SOIL CONSERVATION DISTRICT AT PHONE # AT LEAST 3 DAYS PRIOR TO CONSTRUCTION TO ARRANGE A PRE-CONSTRUCTION MEETING
- A CONSERVATION TECHNICIAN SHALL SET CUT/GRADE STAKES AT THE CONTRACTORS REQUEST
- A CONSERVATION TECHNICIAN MUST BE PRESENT AT THE TIME OF PIPE INSTALLATION, IF REQUIRED

CONSTRUCTION SEQUENCE:

- Contact the soil conservation district at PHONE # to arrange a pre-construction meeting.
- Contact miss utility at 1-800-257-7777
- Install dewatering basin
- Install pump around device
- Excavate area for proposed crossing •
- Install filter fabric, slats, and rock
- Stabilize all disturbed areas per vegetative stabilization methods • and materials
- Remove all erosion and sediment control measures

USER TO UPDATE SEQUENCE AS NEEDED

CRITICAL INSPECTION ITEMS

(Pre-Cast Ford Crossing)

3/20/15

- The landowner will arrange for a pre-construction meeting between the contractor, NRCS and landowner to review 1
- the plans, standards and specifications prior to the start of construction. There will be no changes in specifications, dimensions, or materials unless approved by the engineer responsible
- for this drawing. The drawings are prepared cooperatively by the Natural Resources Conservation Service for named 3. owner/operator. Construction found not in accordance with these drawings and specifications shall violate the cooperative agreement and all drawings, specifications, and Quantities Estimate shall immediately be returned to

the local NRCS office. The following is a list of items that must be inspected by the Technician-in-Charge. If cost share is involved, 4.

Preconstruction Meeting	Date:	Initials:
Verify layouts:	Date:	Initials:
Verify all subgrades:	Date:	Initials:
Verify all subgrade materials CR-6 etc:	Date:	Initials:
Concrete Panels:		
Type and Size:	Date:	Initials:
Foundation:	Date:	Initials:
Placement:	Date:	Initials:
Cutoff Keyway:		
Width and Depth of Keyway:	Date:	Initials:
Riprap Size and Gradation:	Date:	Initials:
Placement of Riprap Fill:	Date:	Initials:
Additional Riprap Placement (If applicable)		
Foundation (properly undercut):	Date:	Initials:
Geotextile material and placement:	Date:	Initials:
Riprap gradation and depth:	Date:	Initials:
Final Backfill placement and grading	Date:	Initials:
Fencing:	Date:	Initials:
Type and Materials:	Date:	Initials:
Proper location:	Date:	Initials:
Installation:	Date:	Initials:
All disturbed areas seeded and mulched:	Date:	Initials:
Other items shown on the plans:	Date:	



THE

INSPEC

CONST

VERIFIE CONSER

AS

0 I CE ΒY SO CO ТО UN




Know what Cal "The Soil Conservation E

existence or Non-existence Shown on these constru have been identified. It is operators and contracto exists or da

SITE DAT


LANDOWNER

CONTACT PE



Construction Landowner's

LANDOWNER - SITE NAME 578 STREAM CROSSING






LOCATION MAP 200 200 400 Scale in Feet

USER TO INSERT SHEET LIST TABLE

	TATEMENT		υ			
THE CONSERVATION PRACT NRCS STANDARDS A	ICE(S) MEETS OR		Date 			
PECTED BY	IATURE	DATE				
	NATURE	DATE				
	JATURE	DATE				
AS BUILT CONTRACT ITEMS:	Reportable Amount	Contract Amount			1	-
				Drawn	Checked	Approved
				Drawn	Che	
			_			Maryland
			_			, Mai
USER TO ENT	ER PRACTICES					ł
OWNER/CONTRACT	OR STATEME	NT		1		
I CERTIFY THAT THIS DESIGN F					ct	
BY A REPRESENTATIVE OF TH SOIL CONSERVATION DISTRIC	T, AND I UNDERSTA			Ç	District	
CONTENTS, ALL CONSTRUCTION TO THESE PLANS AND SPECIF	ICATIONS, I FURTHE	R				
UNDERSTAND THAT ALL CONS INSPECTION OF THIS OFFICE.	TRUCTION WILL BE	UNDER THE	Ц Н 0	-	vation	
OWNER/OPERATOR SIGNATUR	RE DATE) ##	C	CLASS #
CONTRACTOR'S SIGNATURE	DATE			- #]	C0	OB CI
	All disturbed areas to be st completion, using the follow				COUNTY Soil Consei	Ŋ
	Tall Fescue Perennial Ryegrass <u>or</u>	65 lb/ac 5 lb/ac		ך כ	NU	
	Redtop (tolerates moist site White Clover 20-40-40 Fertilizer Ground lime 50% oxides	es) 2 lb/ac 5 lb/ac 500 lb/ac 3 tons /ac			00	
	Straw Mulch Dates listed are for pla	2 tons/ac	-	j		
all before you dig.	Seedin March 1 tł	g Dates nru May 15 ru October 1				
construction drawings are those utilities which	It is the landowner respons State, and Federal permits	that may be needed, and				ŧ
ntractors to assure themselves that no hazard s or damage will occur to utilities"	to maintain this structure a USER TO ENTE	R SEEDING INFO	C			FRACT #
	* For bidding				-1	TR/
ATA:	<u></u>		tes	it of		ce
			States	epartment griculture	S S	
<u>IER INFORMATION:</u> <u>ST</u>	REAM CLASSIFIC	<u>JATION:</u>	United	part ricul		Sel
			Π	De		ition Servi
USER TO ENTER					Re	vati
PERSON:	STREAM CLOSU	IRE DATE(S):			lra	S
					Vati	Son On
			File	Name		
			MD_005	0_Stream	Cross	sing.d
STURBED ACRES = ± STURBED SQFT = ±			Drav	wing No MD_0		
on supervision by NRCS/MDA/ r's permission for MDE and CC	•		She		_	4
					U 1	-

USER TO ENTER PLAN VIEW

Ν



USER TO ENTER CROSS SE

CROSS SECTI


BENCH MARK DESCRIPTIONS


TBM #1 (IP): Elev = ???.?? Top of 1" X 2" wooden hub, marked by witness lath.


TBM #2: Elev = ???.?? Top of 1" X 2" wooden hub, marked by witness lath, near NW corner of building.


TBM #3: Elev = ???.?? Top of bolt in NW corner of concrete. USER TO ENTER PROFILE **PROFILE VIEW**


	Designed Date Drawn Drawn Checked , Maryland Approved
E	LANDOWNER - SITE NAME #### COUNTY Soil Conservation District JOB CLASS#
	TRACT #
	United States Department of Agriculture Natural Resources Conservation Service
SECTION	File Name
ION	Drawing No. MD_0050
	Sheet 2 of 4
























Maryland's Guidelines To Waterway Construction DETAIL 1.3: CULVERT PIPE W/ ACCESS ROAD










EROSION AND SEDIMENT CONTROLS





CRITICAL INSPECTION ITEMS (Culvert Stream Crossing) 6/22/15

The landowner will arrange for a pre-construction meeting between the contractor, NRCS and landowner to review the plans, standards and specifications prior to the start of construction.

- 2. There will be no changes in specifications, dimensions, or materials unless approved by the engineer responsible
- <u>for this drawing.</u>
- 3. The drawings are prepared cooperatively by the Natural Resources Conservation Service for named owner/operator. Construction found not in accordance with these drawings and specifications shall violate the cooperative agreement and all drawings, specifications, and Quantities Estimate shall immediately be returned to the local NRCS office.
- 4. The following is a list of items that must be inspected by the Technician-in-Charge. If cost share is involved, payment may be forfeited if the Technician-in-Charge does not inspect all of the below:

payin	Preconstruction Meeting	Date:	
•	Verify layouts:	Date:	
•	Verify all subgrades:		
•		Date:	
•	Verify all subgrade materials CR-6 etc:	Date:	I
•	Verify Pipe Placement: Correct Size of Culvert Pipe:	Detei	
	Invert Elevations:	Date:	
	Pipe Material and Size:	Date:	
		Date:	
	Proper Joints (Water Tight):	Date:	
	Pipe Anchor Installation: Backfill and compaction:	Date:	
	-	Date:	
•	Placement of Fill and Grading:	Date:	I
•	Placement of Riprap:	Data	
	Inspect Foundation:	Date:	
	Geotextile placement and Type:	Date:	
	Gradation and Placement of Rip Rap:	Date:	I
•	Placement of Walkway or Travel Lane:		
	Inspect Foundation:	Date:	
	Geotextile placement and Type:	Date:	
	Gradation and Placement of stone:	Date:	
•	Final Grading:	Date:	
٠	Fencing:	Date:	
	Type and Materials:	Date:	
	Proper location:	Date:	
	Installation:	Date:	
•	All disturbed areas seeded and mulched:	Date:	I
•	Other items shown on the plans:	Date:	I





ACCESS LANE Not to scale

elow:		
Initia	als:	_
Initia		_
Initia	als:	-
Initia	als:	-
Initia	als:	_
Initia	als:	-
		 -
Initia	als:	-
Initia		-
Initia	als:	-
Initia	als:	-
Initia		_
Initia		-
Initia	als:	-
Initia	als:	-
Initia		-
Initia	als:	 -
Initia	als:	-
Initia	als:	-
Initia		-
Initia	als:	_

_	
_ Initials:	
Initials:	

___ Initials: ____